

# Traffic Management Plan

SAMPLE

**Table of Contents**

Purpose and Scope .....	5
Objectives.....	5
Definitions.....	5
Key Terms .....	5
Roles and Responsibilities.....	6
PCBU / Directors / Senior Management .....	6
Project Manager / Site Manager.....	6
Supervisors / Leading Hands .....	7
Workers and Contractors.....	7
Plant Operators and Drivers.....	7
Traffic Controllers / Spotters.....	7
Consultation, Communication and Training.....	8
Consultation .....	8
Communication.....	8
Training and Competency.....	8
Hazard Identification and Risk Assessment .....	8
Typical Traffic Hazards .....	8
Risk Assessment Process.....	9
Traffic Management Planning .....	9
Site layout and Traffic Flow .....	9
Traffic Guidance Schemes (TGS).....	10
Control Measures – General Principles.....	10
Hierarchy of Control .....	10
Vehicle and Plant Movement Controls .....	11
Access and Egress .....	11
Internal Traffic Routes .....	11
Reversing and Blind Spots .....	11
Parking and Staging Areas.....	11
Pedestrian Management.....	12
Separation from Vehicles .....	12

Site Access for Pedestrians.....	12
High-Risk Activities.....	12
Exclusion Zones and Restricted Areas.....	12
Establishing Exclusion Zones.....	12
Managing Exclusion Zones.....	13
Signage, Barriers and Delineation.....	13
Signage.....	13
Barriers and Fencing.....	13
Delineation.....	13
Deliveries, Loading and Unloading.....	13
Planning Deliveries.....	13
Loading and Unloading Controls.....	14
Specific Industry Examples.....	14
Public and Third-Party Interface.....	14
Managing Risks to the Public.....	14
Property Access.....	14
Environmental and Site Conditions.....	15
Weather and Visibility.....	15
Surface Conditions.....	15
Personal Protective Equipment (PPE).....	15
Monitoring, Inspection and Maintenance.....	15
Routine Inspection.....	15
Checklists.....	15
Maintenance of Controls.....	16
Incident and Emergency Management.....	16
Traffic-Related Incidents.....	16
Emergency Access.....	16
Documentation and Records.....	16
Review and Continuous Improvement.....	17
Appendices.....	17
Appendix 1 – Traffic Risk Assessment Template.....	17
Appendix 2 – Site Traffic Layout Plan (Example Contents).....	17

Appendix 3 – Daily Traffic Management Inspection Checklist..... 18  
Appendix 4 – Roles and Contact Details Register ..... 18

SAMPLE

## Purpose and Scope

This Traffic Management Plan (TMP) sets out the systems, controls and procedures that [Company Name] will implement to eliminate or minimise risks arising from vehicle and mobile plant movements in and around worksites.

It is designed for use across:

- Civil construction and earthworks projects (e.g. roadworks, subdivisions, bulk earthworks)
- Arboriculture and tree services (e.g. tree removals using chippers, EWP, cranes)
- Concrete and formwork operations (e.g. boom pumps, agitators, deliveries)
- Plumbing and gasfitting projects (e.g. trenching services, installations, vac trucks)
- Landscaping works (e.g. skid steer, mini-excavators, tip trucks)
- Building and construction sites (e.g. cranes, telehandlers, delivery vehicles)
- Fencing contractors (e.g. post drivers, augers, material deliveries)

The TMP applies to all workers, contractors, visitors and members of the public who may be affected by [Company Name]'s activities.

## Objectives

The objectives of this Traffic Management Plan are to:

- Identify traffic-related hazards arising from vehicles and mobile plant
- Assess the risks to workers and others, including pedestrians and the public
- Implement effective controls to eliminate or minimise those risks so far as is reasonably practicable
- Provide clear instructions for planning, setting out, monitoring and reviewing traffic management arrangements
- Define roles, responsibilities and communication pathways
- Support compliance with relevant work health and safety legislation, codes of practice and Australian Standards

## Definitions

### Key Terms

- **Traffic Management Plan (TMP)** – A documented plan that details how vehicle and pedestrian movements will be safely managed on and around a worksite.
- **Traffic Guidance Scheme (TGS)** – A diagram showing the layout of signs, cones, barriers and devices used to guide traffic past or through a work area, typically based on AS 1742 and state/territory manuals.

- **PCBU** – Person Conducting a Business or Undertaking, as defined in WHS legislation.
- **Mobile Plant** – Any powered plant that is capable of moving under its own power, such as excavators, skid steers, loaders, cranes, EWPs, telehandlers and forklifts.
- **Pedestrian** – Any person on foot, including workers, subcontractors, visitors and members of the public.
- **Exclusion Zone** – A designated area from which unauthorised persons are excluded due to the risk of plant or vehicle movement.
- **Spotter** – A trained person responsible for directing plant/vehicle movements and ensuring pedestrian separation.

## Roles and Responsibilities

### PCBU / Directors / Senior Management

- Ensure adequate resources are provided to develop, implement and maintain this TMP.
- Verify that traffic management is included in project planning, tendering and pre-start risk assessments.
- Ensure competent persons are engaged to prepare or approve TGS and site-specific traffic arrangements.
- Provide and maintain plant, equipment and traffic control devices that are fit for purpose.
- Ensure workers are trained and competent in traffic management procedures relevant to their role.
- Monitor compliance with the TMP through inspections, audits and consultation.

### Project Manager / Site Manager

- Implement this TMP on all relevant sites and adapt it to specific conditions.
- Ensure a site-specific traffic risk assessment and traffic layout plan are completed before work starts.
- Coordinate with principal contractors, road authorities and utility providers where required.
- Ensure traffic controls (signage, barriers, delineation) are installed, maintained and removed correctly.
- Confirm that all plant operators, truck drivers and subcontractors are inducted into site traffic rules.
- Investigate traffic-related incidents, near misses and non-conformances and implement corrective actions.