

Plastering Rendering and Wet Mix Application | SAFE WORK METHOD STATEMENT (SWMS)

TASK OR ACTIVITY: Plastering Rendering and Wet Mix Application

| | | |
|-------------------|--------|--------|
| Business Name: | ABN: | SWMS# |
| Business Address: | | |
| Contact Person: | Phone: | Email: |

THIS SAFE WORK METHOD STATEMENT IS APPROVED BY THE PCBU OF THE PROJECT

Under the Work Health and Safety Regulation (WHS Regulation), a person conducting a business or undertaking (PCBU) is required to ensure that a safe work method statement (SWMS) is prepared before the proposed work starts.

| | | |
|---|--------|--------|
| Full Name: | | |
| Signature: | Title: | Date: |
| Details of the person(s) responsible for ensuring implementation, monitoring compliance of the SWMS as well as reviews and modifications of the SWMS. | | |
| Full Name: | Title: | Phone: |

ALL PERSONNEL PARTICIPATING IN ANY ACTIVITY ON THIS SWMS MUST HAVE THE FOLLOWING COMMUNICATED

Safety meetings or toolbox talks will be scheduled in accordance with legislative requirements to first identify any site hazards, then to communicate those hazards and then to further take steps to either eliminate or control each hazard.

If an incident or a near miss occurs, all work must stop immediately. Depending on the severity of the incident, a meeting will be called with all workers to amend the SWMS if required. The meeting may also be an educational opportunity.

Any changes made to the SWMS after an incident or a near miss must be approved by the Person Conducting Business or Undertaking and communicated to all relevant personnel.

The SWMS must be kept and be available for inspection at least until the work is completed. Where a SWMS is revised, all versions should be kept. If a notifiable incident occurs in relation to which the SWMS relates, then the SWMS must be kept for at least two years from the occurrence of the notifiable incident.

NAME OF ALL RELEVANT PERSONNEL WHO HAVE BEEN CONSULTED AND COMMUNICATED TO IN THE DEVELOPMENT AND APPROVAL OF THIS SWMS

CLIENT OR PRINCIPAL CONTRACTOR DETAILS

| | |
|--|----------------|
| Client: | SCOPE OF WORKS |
| Project Name: | |
| Project Address: | |
| Project Manager: | |
| Contact Phone: | |
| Date SWMS supplied to Project Manager: | |

ANY HIGH-RISK CONSTRUCTION WORK BEING CARRIED OUT

- | | |
|--|--|
| <input type="checkbox"/> involves a risk of a person falling more than 2 meters | <input type="checkbox"/> is carried out on or near pressurised gas mains or piping |
| <input type="checkbox"/> is carried out on a telecommunication tower | <input type="checkbox"/> is carried out on or near chemical, fuel or refrigerant lines |
| <input type="checkbox"/> involves demolition of an element of a structure that is load-bearing | <input type="checkbox"/> is carried out on or near energised electrical installations or services |
| <input type="checkbox"/> involves demolition of an element related to the physical integrity of a structure | <input type="checkbox"/> is carried out in an area that may have a contaminated or flammable atmosphere |
| <input type="checkbox"/> involves, or is likely to involve, disturbing asbestos | <input type="checkbox"/> involves tilt-up or precast concrete |
| <input type="checkbox"/> involves structural alteration or repair that requires temporary support to prevent collapse | <input type="checkbox"/> is carried out on, in or adjacent to a road, railway, shipping lane or other traffic corridor |
| <input type="checkbox"/> is carried out in or near a confined space | <input type="checkbox"/> is carried out in an area of a workplace where there is any movement of powered mobile plant |
| <input type="checkbox"/> is carried out in/near a shaft or trench deeper than 2m or tunnel involving use of explosives | <input type="checkbox"/> is carried out in areas with artificial extremes of temperature. |
| <input type="checkbox"/> is carried out in or near water or other liquid that involves a risk of drowning. | <input type="checkbox"/> involves diving work. |

ANY HIGH-RISK MACHINERY OR EQUIPMENT NEARBY

RISK MATRIX

| LIKELIHOOD | INSIGNIFICANT | MINOR | MODERATE | MAJOR | CATASTROPHIC | SCORE | ACTION | HEIRARCHY OF CONTROLS |
|---|---------------|---------------|---------------|------------|--------------|----------------|-----------------------------------|--|
| ALMOST CERTAIN | 3 HIGH | 3 HIGH | 4 ACUTE | 4 ACUTE | 4 ACUTE | | | Elimination Remove the hazard. |
| LIKELY | 2 MODERATE | 3 HIGH | 3 HIGH | 4 ACUTE | 4 ACUTE | 4A ACUTE | DO NOT PROCEED | Substitution Replace the hazard. |
| POSSIBLE | 1 LOW | 2 MODERATE | 3 HIGH | 4 ACUTE | 4 ACUTE | 3H HIGH | Review before work starts. | Isolation Isolate People from the hazard |
| UNLIKELY | 1 LOW | 1 LOW | 2 MODERATE | 3 HIGH | 4 ACUTE | 2M MODERATE | Ensure control measures in place. | Engineering Isolate the hazard. |
| RARE | 1 LOW | 1 LOW | 2 MODERATE | 3 HIGH | 3 HIGH | 1L LOW | Monitor and keep records | Administrative Change the work. |
| Notes on Hierarchy of Controls: Elimination methods are the most effective and preferred when controlling a hazard. Substitution is the second most effective method of controlling a hazard. Engineering by isolation is the third most effective, while Administrative Controls by changing the work is the fourth most effective method. PPE (Personal Protective Equipment) is the least effective method. | | | | | | | | PPE |

PERSONAL PROTECTIVE EQUIPMENT (PPE)

Select the appropriate PPE above suitable for the equipment used or the job task being performed (if applicable).

| FOOT PROTECTION | HAND PROTECTION | HEAD PROTECTION | HEARING PROTECTION | EYE PROTECTION | RESPIRATORY PROTECTION | FACE PROTECTION | HIGH-VIS CLOTHING | PROTECTIVE CLOTHING | FALL PROTECTION | SUN PROTECTION | HAIR/JEWELLERY SECURED |
|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
| | | | | | | | | | | | |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Other PPE Required:

Permit or Licenses Requirements

Mandatory Qualifications and Training

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|----------------------------------|---|--------------|---|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| Pre-start planning and induction | <ul style="list-style-type: none"> • Unfamiliar site hazards • Unclear emergency procedures • Inadequate competence for task • Uncoordinated high risk construction work • Fatigue and heat stress | 3H | <ul style="list-style-type: none"> • Review principal contractor WHS management plan and confirm plastering, rendering and wet mix tasks, work areas, site access and traffic flow before work starts • Identify whether high risk construction work applies under WHS Regulations (e.g. work at heights, near live services, in or near traffic corridors) and document associated controls in this SWMS • Conduct a site-specific induction for all workers covering amenities, first aid, emergency assembly point, evacuation routes, fire equipment locations and incident reporting process • Verify each worker holds relevant high risk work licences, VOCs or training for scaffolds, elevated work platforms, powered mixers and cutting tools before allocation of tasks • Consult with workers and subcontractors in a pre-start meeting about planned plastering and rendering activities, sequence of works and interaction with other trades • Confirm work hours to manage fatigue risk and schedule regular drink breaks in shade for hot conditions • Check weather conditions (temperature, wind, rain) and reschedule or modify work where conditions create unsafe surfaces, reduced visibility or extreme heat • Establish exclusion zones around active plastering and sanding areas using barriers or bunting to prevent unauthorised access • Display SWMS and make it readily accessible on site in hard copy or electronic format • Instruct workers to stop work and notify the supervisor immediately if site conditions change, undocumented hazards are identified or controls are not effective | 2M |
| Deliveries and gypsum handling | <ul style="list-style-type: none"> • Manual handling of plasterboard • Crushing by falling sheets • Gypsum dust inhalation • Traffic interaction with delivery vehicles • Sheet edge cuts | 3H | <ul style="list-style-type: none"> • Coordinate delivery times with principal contractor to avoid peak traffic, school zones and major crane operations • Direct delivery vehicles using a dedicated spotter wearing high-visibility clothing; DO NOT allow reversing without a spotter where pedestrians are present • Inspect delivery area for overhead services, unstable ground and trip hazards before unloading plasterboard, gypsum bags or premix tubs • Use mechanical aids such as trolleys, panel lifters or forklifts to move plasterboard sheets and gypsum bags wherever practicable; DO NOT manually carry excessive loads • Team-lift large or awkward items using correct lifting technique, keeping the load close to the body and avoiding twisting while carrying • Stack plasterboard sheets flat on level bearers, no higher than shoulder height, and chock the stack to prevent sliding or toppling • Store gypsum powder bags in a dry, well-ventilated area, off the ground on pallets, and protect from moisture ingress • Wear cut-resistant gloves when handling plasterboard to reduce risk of lacerations from sheet edges | 2M |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|----------------------------------|---|--------------|---|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | | | <ul style="list-style-type: none"> • Wear a P2 disposable respirator compliant with AS/NZS 1716 when handling dusty gypsum powder or damaged boards that generate fine dust • Sweep or vacuum gypsum dust using a HEPA-filter vacuum cleaner; DO NOT use compressed air to clean down dusty surfaces | |
| Site preparation and access | <ul style="list-style-type: none"> • Slips on wet or uneven surfaces • Trips on offcuts and hoses • Contact with live electrical services • Unstable access equipment • Poor lighting in work area | 3H | <ul style="list-style-type: none"> • Inspect work area for uneven ground, loose debris, floor penetrations and wet surfaces before commencing and at the start of each shift • Remove offcuts, discarded pipe rolls and waste from access paths; maintain minimum 1 m clear walkway to all exits • Confirm electrical supply locations with builder and review latest plans before drilling or fixing to walls and ceilings • Use cable and service locators or computer-aided drawings before fixing long screws or anchors into walls that may conceal services • Isolate and tag off inaccessible electrical circuits where work may contact live wiring; DO NOT drill or screw into walls known to contain live services • Install temporary lighting where natural light is inadequate, ensuring all portable lights are low-voltage or LED-protected • Select step ladders or platform ladders rated to AS/NZS 1892 and confirm they are in good condition before use • Position ladders on firm, level surfaces, fully open and locked, with three points of contact maintained during use • Set up portable work platforms or mobile scaffolds for extended overhead work instead of overreaching from ladders • Barricade floor penetrations and stair voids adjacent to plastering work using guardrails or covers capable of withstanding expected loads | 2M |
| Scaffolds and working at heights | <ul style="list-style-type: none"> • Falls from scaffold decks • Falls from ladders • Falling tools and materials • Scaffold collapse • Overreaching from platforms | 4A | <div>REDACTED</div> <div>REDACTED</div> <div>REDACTED</div> <div>REDACTED</div> <div>REDACTED</div> <div>REDACTED</div> | 2M |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|------------------------------|---|--------------|--|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| Preparing mix for plastering | <ul style="list-style-type: none"> • Contact with wet cementitious materials • Exposure to airborne dust • Manual handling of water and mix bags • Splash to eyes and skin • Electric shock from powered mixer | | | 2M |
| Operate a plaster mixer | <ul style="list-style-type: none"> • Entanglement in rotating parts • Noise exposure from machinery • Flying debris from mixing • Inadvertent start-up • Strains from moving equipment | 3H | | 2M |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|--------------------------------------|---|--------------|--|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| | | | [REDACTED] | |
| Plastering walls and rendering works | <ul style="list-style-type: none"> • Repetitive strain from trowel use • Muscle fatigue from prolonged work • Contact with sharp edges and corners • Slip hazards from spilled wet material • Eye irritation from splashes | 3H | [REDACTED] | 2M |
| Bone hawk use and trowelling | <ul style="list-style-type: none"> • Dropped hawk or trowel • Hand and wrist overuse | 3H | [REDACTED] | 2M |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|------------------------------------|---|--------------|--|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | <ul style="list-style-type: none"> • Imbalance while loading hawk • Lacerations from tool edges • Struck by during passing tools | | <div>SAMPLE</div> | |
| Tape jointing and finishing joints | <ul style="list-style-type: none"> • Neck and shoulder strain • Dust from joint compound • Skin contact with additives • Eye irritation from splatter • Falls from working at height | 3H | <div>SAMPLE</div> | 2M |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|-----------------------------------|--|--------------|---|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | | | | |
| Patching holes and repairs | <ul style="list-style-type: none"> • Exposure to hidden services • Sharp broken plasterboard edges • Silica dust from cutting repairs • Working on ladders • Eye injury from scraping | 3H | <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> | 2M |
| Drywall and plaster joint sanding | <ul style="list-style-type: none"> • Inhalation of fine dust • Eye irritation from airborne particles • Noise from sanding equipment • Electric shock from power sanders • Falls from platforms while sanding | 4A | <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> <p>[REDACTED]</p> | 2M |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|--|--|--------------|--|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | | | | |
| Handling, cleaning and disposal of materials | <ul style="list-style-type: none"> • Manual handling of waste • Contamination of stormwater • Slips on leftover plaster • Contact with sharp offcuts • Uncontrolled dust during clean-up | 3H | | 2M |
| General health, PPE and emergency response | <ul style="list-style-type: none"> • Noise-induced hearing loss • Respiratory illness from dust • Eye injuries from splashes and dust • Heat stress and dehydration • Delayed response to incidents | 3H | | 1L |

| JOB STEP | POTENTIAL HAZARDS | IR | CONTROL MEASURES | RR |
|---------------------|------------------------|--------------|---|---------------|
| SPECIFIC WORK STEPS | HAZARDS THAT MAY ARISE | INITIAL RISK | SPECIFIC MEASURES TO BE PUT IN PLACE TO ELIMINATE OR CONTROL THE RISKS | RESIDUAL RISK |
| | | | <div></div> <div></div> <div></div> <div></div> <div></div> <div></div> | |
| | | | | |

SAMPLE

EMERGENCY RESPONSE – CALL 000 FOR EMERGENCIES

Ensure to have an Emergency Management Plan in place as well as adequate numbers of trained first aid staff with easy access to fully stocked first aid kits, rescue equipment, material safety data sheets, adequate access to emergency communication equipment and fire-fighting equipment suitable for all classes of fire and ignition sources.

LEGISLATIVE REFERENCES

RELEVANT LEGISLATION AND CODES OF PRACTICE. DELETE THE LEGISLATIVE REFERENCES IF ANY STATE THAT ARE NOT APPLICABLE

Queensland & Australian Capital Territory

Work Health and Safety Act 2011

Work Health and Safety Regulations 2011

Legislation QLD: <https://www.worksafe.qld.gov.au/laws-and-compliance/work-health-and-safety-laws>

Codes of Practice QLD: <https://www.worksafe.qld.gov.au/laws-and-compliance/codes-of-practice>

Legislation ACT: <https://www.worksafe.act.gov.au/laws-and-compliance/acts-and-regulations>

Codes of Practice ACT: <https://www.worksafe.act.gov.au/laws-and-compliance/codes-of-practice>

Victoria

Occupational Health and Safety Act 2004

Occupational Health and Safety Regulations 2017

Legislation VIC: <https://www.worksafe.vic.gov.au/occupational-health-and-safety-act-and-regulations>

Codes of Practice VIC: <https://www.worksafe.vic.gov.au/compliance-codes-and-codes-practice>

New South Wales

Work Health and Safety Act 2011

Work Health and Safety Regulations 2025

Legislation NSW: <https://www.safework.nsw.gov.au/legal-obligations/legislation>

Codes of Practice NSW: <https://www.safework.nsw.gov.au/resource-library/lis>

Western Australia

Work Health and Safety Act 2020

Work Health and Safety Regulations 2022

Legislation Western Australia: <https://www.commerce.wa.gov.au/worksafe/legislation>

Codes of Practice WA: <https://www.commerce.wa.gov.au/worksafe/codes-practice>

Northern Territory

Work Health and Safety (National Uniform Legislation) Act 2011

Work Health and Safety (National Uniform Legislation) Regulation 2011

Legislation NT: <https://worksafe.nt.gov.au/laws-and-compliance/workplace-safety-laws>

Codes of Practice NT: <https://worksafe.nt.gov.au/factsheets-and-resources/codes-of-practice>

Safe Work Australia Links

Law and Regulation (All States): <https://www.safeworkaustralia.gov.au/law-and-regulation>

Model Codes of Practice: <https://www.safeworkaustralia.gov.au/resources-publications/model-codes-of-practice>

Model Codes of Practice

- Managing noise and preventing hearing loss at work
- Confined spaces
- Labelling of workplace hazardous chemicals
- Managing risks of hazardous chemicals in the workplace
- Welding processes
- First aid in the workplace
- Managing the risk of falls at workplaces
- Hazardous manual tasks
- Managing the risk of falls in housing construction
- Managing electrical risks in the workplace
- Demolition work
- Excavation work
- Work health and safety consultation, cooperation and coordination
- Managing the work environment and facilities
- How to manage work health and safety risks
- Managing risks of plant in the workplace
- Construction work

South Australia

Work Health and Safety Act 2012 (SA)

Work Health and Safety Regulations 2012 (SA)

Legislation for SA: <https://www.safework.sa.gov.au/resources/legislation>

Codes of Practice for SA: <https://www.safework.sa.gov.au/workplaces/codes-of-practice#COPs>

Tasmania

Work Health and Safety Act 2012

Work Health and Safety (Transitional and Consequential Provisions) Act 2012

Work Health and Safety Regulations 2012

Work Health and Safety (Transitional) Regulations 2012

Legislation for TAS: <https://worksafe.tas.gov.au/topics/laws-and-compliance/acts-and-regulations>

Codes of Practice for TAS: <https://worksafe.tas.gov.au/topics/laws-and-compliance/codes-of-practice>

Details of permits, licenses or access required by regulatory bodies (add or delete as required):

- Permits from local council
- Authorisation to commence work
- Any required documents.

SIGNATORIES OF THE SAFE WORK METHOD STATEMENT

The signed and dated personnel listed below have cooperated in the consultation and development of this Safe Work Method Statement which has been approved by the Person/s Conducting a Business or Undertaking (PCBU). In signing this Safe Work Method Statement each individual acknowledges and confirms that they have read this SWMS in full, having raised any questions for items on this Safe Work Method Statement that require clarification, and confirms that they are competent, skilled and knowledgeable for the task assigned to them. Every person acknowledges that they have received the relevant training and qualifications where required, before carrying out any work contained in this Safe Work Method Statement. By signing this Safe Work Method Statement each individual agrees to work safely, to follow any safe work instructions which are provided, and agrees to use all Personal Protective Equipment where appropriate.

| Worker Name | Signature | Date |
|-------------|-----------|------|
| | | |
| | | |
| | | |
| | | |
| | | |

SAFE WORK METHOD STATEMENT MONITORING AND REVIEW

The SWMS must be reviewed regularly to make sure it remains effective and must be reviewed (and revised if necessary) if relevant control measures are revised. The review must be carried out in consultation with workers (including contractors and sub-contractors) who may be affected by the operation of the SWMS and their health and safety representatives who represent that work group at the workplace.

When the SWMS has been revised the PCBU must ensure that all persons involved with the work are advised that a revision has been made and how they can access the revised SWMS, including all persons who will need to change a work procedure or system as a result of the review are advised of the changes in a way that will enable them to implement their duties consistently with the revised SWMS. All workers that will be involved in the work must be provided with the relevant information and instruction that will assist them to understand and implement the revised SWMS.

The SWMS must be monitored regularly for the effectiveness of ensuring hazard controls are effective in reducing the risk of incidents, keeping the workplace safe for all personnel. The person responsible for monitoring the effectiveness of the Safe Work Method Statement should employ a multi-faceted approach which includes but is not limited to:

1. Spot Checks.
2. Consultation with workers, contractors and sub-contractors.
3. Internal audits on a continual basis.

An approach of continuous improvement, promptly recording inconsistencies or deficiencies, followed up by immediate corrective action and consultation with all relevant personnel ensures that the PCBU is consistently developing ever-improving systems of safe work principles.

| REVIEW NUMBER | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
|---------------|---|---|---|---|---|---|---|
| NAME | | | | | | | |
| INITIALS | | | | | | | |
| DATE | | | | | | | |

SAFE WORK METHOD STATEMENT REVIEW CHECKLIST

This Safe Work Method Statement Review Checklist is to be followed and used upon initial development of the SWMS to help ensure that all steps have been adequately taken before work commences. Think of this document as an internal audit review checklist before commencing work, and may form part of a Toolbox Talk (safety meeting) and may be used as an opportunity for education and training.

| ITEMS WHICH MUST BE INCLUDED IN THE SWMS | COMPLETED | COMMENTS |
|--|-------------------------------------|-----------------------|
| The company details have been entered, including the project name and address. | <input checked="" type="checkbox"/> | |
| All relevant personnel consulted during the development of the SWMS. | <input checked="" type="checkbox"/> | |
| Name, signature, position and date signed of the person approving the SWMS. | <input type="checkbox"/> | |
| Specific personnel and qualifications, experience is noted in the SWMS. | <input checked="" type="checkbox"/> | |
| Provides a step-by-step process of tasks required to carry out the activity or task. | <input checked="" type="checkbox"/> | |
| Adequate risk assessment of any identified hazards has been completed. | <input checked="" type="checkbox"/> | |
| Foreseeable hazards are identified and documented for each step. | <input checked="" type="checkbox"/> | |
| Any hazards listed in any site risk assessments have been added to the SWMS. | <input checked="" type="checkbox"/> | |
| SWMS initial risk (IR) column as well as residual risk (RR) column completed. | <input checked="" type="checkbox"/> | |
| Check control measures added to the SWMS are the most effective selected. | <input checked="" type="checkbox"/> | |
| Responsible person is assigned and listed on the SWMS for the implementation of control measures. | <input checked="" type="checkbox"/> | |
| Permit or licenses requirements specified, such as Hot Work, Electrical Work, Work at Heights etc. | <input checked="" type="checkbox"/> | |
| SWMS identifies plant and equipment to be used. | <input checked="" type="checkbox"/> | |
| Details of inspection checks required for any equipment listed and noted on the SWMS. | <input checked="" type="checkbox"/> | |
| Describes any mandatory qualifications, experience, training or skills required to perform the work. | <input checked="" type="checkbox"/> | |
| Applicable personal protective equipment is selected on the SWMS. | <input checked="" type="checkbox"/> | |
| Reflects and documents any legislative references and/or Australian Standards. | <input checked="" type="checkbox"/> | |
| Identifies any hazardous substances used with specific control measures in line with any SDS. | <input checked="" type="checkbox"/> | |
| | | |
| REVIEWED BY | | DATE REVIEWED |
| SIGNATURE | | DATE COMPLETED |